

15-051-05751-0000

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 14-29
LOCATION SW NW SE
SEC. 18 TWP. 11 RGE. 16

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease M.P. Cress ANB KCC

Operator Skelly Oil Co Address Box 391 Hutchinson

Field Bemis County Ellis

Total Depth 3342 Feet.

Plugging Contractor Shull pipe pulling Co

Plugging Contractor's License No. 8

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 992 Circulated with 475 sax cement - 5 1/2" at 3330'

with 150 sax cement behind - cement to 3320' - perforations at 3312'.

Filled with sand to 3300', set 4 sax cement with dump bailer, pulled 2450' 5 1/2", heavy mud to 300', rock bridge and 25 sax cement, mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 18 T 11 R 16
BOOK PAGE 14 LINE 29

STATE OF KANSAS
RCWO
MAR 1 - 1954
03-01-54
CONSERVATION DIVISION
Wichita, Kansas

Edwin Perry
District Conservation Agent
Date 2-25-54