

15-051-03285-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 4 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Lario Oil & Gas Company

Complete Address 301 South Market, Wichita, Kansas 67202

Lease Name Romine Well No. 2

Location SW SW NW Sec. 18 Twp. 11 Rge. (E) (W) 166

County Ellis Total Depth 3310'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:15 A Day 31 Month 10 Year 1974

The above well was plugged as follows:

Total Depth 3310' 10 3/4 csg set at 1005' cwc 400 sk.

7" csg set at 3305' cw 125 sx cem.

7" csg PBTD 3178' W/castiron plug.

Filled 7" csg with sand (3178-3100) dumped 5 sk cmt W/dump bailer. (3100-3070)

Cutoff & recovered 2600' of 7" csg.

Filled 10 3/4 csg with mud to 315' -set rock & sand bridge (315-300)

Filled with RM cem. from 300' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/4/74

INV. NO. 238-W

Signed: Leo Massey  
Well Plugging Supervisor