

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 100-5

LOCATION SE-NW-NW

SEC. 18 TWP. 11 RGE. 16-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease Monica

Operator Republic Natural Gas Co. Address Box # 126 Elliswood-Haus-

Field _____ County Ellis

Total Depth 3303 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 976 ft. Circulated with cement
7 casing set at 3297 ft. 100 sacks of cement.
3rd tubing shot of at 2723 ft. & pulled out. Set Rock
Bridges & 15 sacks of cement at 2710 ft. mud to 250 ft
Rock Bridges & 20 sacks of cement at 250 ft. mud
to 235 ft. Plug & 10 sacks of cement at the
surface.

Pipe Pulling, Inc. Plugging Contractors

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1951

RCUD
08-24-51

CONSERVATION DIVISION

C. Wichita, Kansas

District Conservation Agent

PLUGGING
FILE SEC. 18 T. 11 R. 16 W
BOOK. PAGE 100 LINE 5

Date 8-22-51