

15-051-19306-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 1130 Wichita Plaza Wichita, Kans

Lease Name Cress Well No. 1

Location NE NE SW Sec. 18 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3352

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Operation Completed: Hour 5PM Day 13 Month 1 Year 64

The Above well was plugged as follows:

8 5/8" 801' circulated with cement - 5 1/2" 3341' with 100 sax cement
Sand back to 3330', set 4 sax cement with dump bailer.

Pulled 2725' 5 1/2" to 325' - shut in head and pumped 35 sax gel through
5 1/2" - 400# pump pressure - released pressure and displaced 50 sax cement
through 5 1/2" at 325', heavy mud to 35', cement to bottom cellar.

Mudding and cementing by Southwest Casing Pulling pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edson Kelly*
Well Plugging Supervisor

DATE 1/15/64

INV. NO. 8461-W