

15-051-19307-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 14 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers-KSB&T Bldg., Wichita, Kansas 67202

Lease Name Cress "A" Well No. 11

Location SE SE SE Sec. 18 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3338'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 3 P Day 12 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 3338' 8 5/8 csg set 988' cwc 450 sx.

5 1/2 csg set 3336' cw 175 sk cem. Top perf. (2972')

Filled 5 1/2 csg W/sd (3338-2950) dumped 4 sk cem W/dump bailer. (2950-2920)

Cutoff & recovered 2126' of 5 1/2 csg.

Drlg. mud to 330' -set rock & sand bridge (330-320)

Mixed & dumped 25 sk cement. (320-245) Filled with mud (245-40)

Rock & sand bridge (40'-35') Mixed & dumped 10 sx cem. (35' to base of cellar.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo L. Mauer
Well Plugging Supervisor

DATE 3/14/75

INV. NO. 1011-W