

15-051-05745-0001

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
MAY 17 1960
CONSERVATION DIVISION
Wichita, Kansas
RCUO
05-17-60

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: NE NW NW Sec. 18 Twp. 11 Rge. 16 (E) (W)

Name of Field: Romine Total Depth: x2 3845

I have this date completed supervision of plugging of:

Lease Name: Romine Well No. 2

Operator's Full Name: Republic Natural Gas

Complete Address: Box 126 Ellinwood, Kans

Plugging Contractor: Same & Globe Cementing Co

Address: _____ License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well x D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No x

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 12 Month 5 Year 60

The above well was plugged as follows:

16" 101' circulated with cement - 10" 985' with 410 sax cement behind-

7" 3298' with 125 sax cement behind and filled to 0" in annulus with gel

mud - 184' 5 1/2" liner - set at 3450' cemented - 78 jts 3" tubing with

packer lost in hole - top 3" 850' - hole in 7" 7'

Pumped hole full heavy mud (30 sax weight mud), pumped 130 sax cement

in 7" - pumped 120 sax cement in annulus 7" to 10". Cement to 0' - No Rec.

Mudding and cementing by Globe Cementing Co

Signed: Leon Perry
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 5/17/60
WV. NO. 1574-W