

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22625-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Jolly J., Inc.

Complete Address Box 572, Russell, Kansas 67665

Lease Name Cress Well-No. #1

Location NE/SW/SE Sec. 18 Twp. 11 Rge. 16 (East) (West)

County Ellis Total Depth 3400'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations

Address Box 506, Russell, Kansas 67665 License No. _____

Operation Completed: Hour: 10:15PM. Day: 26th Month: Oct. Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-250' s.p. cnc. w/150 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-6% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 660' w/70 sacks cement

2nd plug @ 240' w/40 sacks cement

3rd plug solid bridge of hulls and plug @ 40' w/10 sacks cement

10 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were followed as herein stated.

DATE 10-17-81

Signed: [Signature]
Conservation Division Agent

INV. NO. 8297W
8371-W