

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 25 TWP. 11S RGE. 18W E/W
Location as in quarters or footage from lines:
NW/4 NE/4 NE/4

Lease Owner Isern-Schultz Oil & Gas, Inc.
Lease Name Marshall #5 Well No. _____
Office Address P.O. Box 486 Ellinwood, Kansas 67526
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 5-5-82
Plugging completed 5-10-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
Producing formation _____ Depth to top _____ bottom _____ T.D. 3506'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1266'	none
				5-1/2"	3501'	1678'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged bottom off with sand to 3456' and ran 5 sacks cement. Shot casing @2491',
pipe parted, pulled 53 joints of 5-1/2" casing. Plugged well with 5 sacks hullo, 19
sacks gel, 8-5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% ee.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 1982

My Commission expires:



Irene Hoover
Notary Public
RECEIVED
MAY 13 1982
05-13-82
CONSERVATION DIVISION
Wichita Kansas

WELL LOG

G. W. Keyes Drilling Co. et al, Owners - Marshall #5
NW/4 NE/4 NE/4 Section 25, Township 11S, Range 18 West,
Ellis County, Kansas

Figures indicate bottom of formation

Elevation	1998 DF	0	to	615	shale and shells
				750	pyrite
				940	sandy shale
Casing Record:				1090	shale
8 5/8" set at 1266'				1190	shale and shells
5 1/2" set at 3501' DF				1245	shale and red bed
				1285	anhydrite
				1830	shale and shells
				1900	shale and lime
				1995	broken lime
Heebner shale	3184			2135	lime and shale
Lansing (shite)	3224			2345	lime
Simpson	3494			2495	lime and shale
Arbuckle	3499			2575	lime
				2995	shale and lime
Rotary commenced	4-25-48			3506	lime
completed	5-9-48			3506	Total rotary depth

Cable tools commenced 5-11-48
Completed 6-14-48

CABLE TOOL WORK

Moved in cable tools, bailed hole, drilled cement, drilled deeper.

RECEIVED
STATE CORPORATION COMMISSION
3521 lime
3521 Total Depth DF

STATE OF KANSAS)
COUNTY OF BARTON) SS

RCVD
APR - 5 1949
04-05-82
CONSERVATION DIVISION
Wichita, Kansas

I, G. W. Keyes, Part Owner of the above described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

Subscribed and Sworn to before me this 25th day of November, 1949.

G. W. Keyes
George A. Meyer
Notary Public

My commission expires Feb. 10, 1951.