


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-05745-0001
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 18 Twp. 11 Rge. 16 (E) W (W)
Location as "NE/CNW/SWK" or footage from lines NE/4 NW/4 NW/4
Lease Owner Republic Natural Gas Company
Lease Name Romine Well No. 2
Office Address Box 367, Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) S.W.D.W.
Date well completed October 25 1943
Application for plugging filed Verbal authority May 4 1960
Application for plugging approved Approved by Eldon Petty May 4 1960
Plugging commenced May 11 1960
Plugging completed May 13 1960
Reason for abandonment of well or producing formation Casing failure

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Granite Wash Depth to top 3837 Bottom 3845 Total Depth of Well 3845 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
Clay - sand		0	101	16" OD	101'	None
Shale - shells		0	985	10-3/4" OD	985'	None
Lime		0	3298	7" OD	3298'	None
Lime		3245	3429	5-1/2" OD	184'	None
Granite wash		3837	3845			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3-1/2" OD tubing in well from 837' to 3390' with packer set at 3390'.
May 11, 1960 - Mixed 30 sacks mud and pumped down 7" casing at 0# pressure. Mixed 130 sacks and pumped down 7" casing at 0# pressure. Mixed 120 sacks cement and pumped down annulus, pressure at start 175#, pressure at end 0.
Ran measuring line after 24 hours and found top of cement at 41' from surface. Filled the 41' in 7" with crushed rock and mixed one sack of cement and put on top May 13, 1960.

RECEIVED
STATE CORPORATION COMMISSION
JUN 8 1960
CONSERVATION DIVISION
Wichita, Kansas
PCWD
06-08-60

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Cementing Company
Address Plainville, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
P. B. Horst (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P. B. Horst
Box 367, Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of June, 19 60
My commission expires 8-20-63
Y. M. Stumm
Notary Public.

