

15-057-00410-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 18 Twp. 11S Rge. 16 (X) (W)

Location as "NE/CNW/SW" or footage from lines NE SE NE

Lease Owner Frontier Oil Co.

Lease Name Miller Well No. 1

Office Address 321 E. Williams Ave. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 6/15/56 19

Application for plugging filed 6/14/56 19

Application for plugging approved 6/14/56 19

Plugging commenced 6/15/56 19

Plugging completed 6/15/56 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3420 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1022	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud from 3420 to cellar. Put in wood plug. Put on swedge. Pumped in 80 sacks cement by Sun Cementers. Job complete 3 a.m. 6/15/56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.

Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

S. P. Hall (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. P. Hall

(Address) _____

SUBSCRIBED AND SWORN to before me this 18th day of June, 1956

My commission expires 1-30-57.



Margie Cooper Notary Public.

RECEIVED
STATE CORP COM
RWG
JUN 20 1956
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 18 T 11 R 16W
BOOK PAGE 72 LINE 29

15-051-00410-0000

FRONTIER OIL CO. NE SE NE 18-11S-16W
 Miller #1 Ellis County, Kansas
 Sierra Petroleum Co., _ Contr. , Elev: 1807 DF
 1810 KB
 Total Depth: 3420* D&A
 Comm: 6/3/56
 Comp: 6/15/56
 Casing: Cement:
 8 5/8 @ 1022 with 400 sks Bulk

FORMATION	DEPTH
Salt Sand & Gravel	105
Shale	150
Sand	210
Shale & shells	440
Sand, shale & pyrite	550
Shale, shell & pyrite	655
Shale & pyrite	745
Red Bed	1012
Anhydrite	1040
Shale, shells & pyrite	1375
Shale & salt	1510
Shale & lime	2320
Lime	2375
Lime & shale	2967
Lime	3373
Conglomerate	3392
Arbuckle	3420
Tops: Heebner	2986
Toronto	3012
Kansas City	3032

STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)


I hereby certify that the above information is true and correct to the best of my knowledge.

S. P. Hall

Subscribed and sworn to before me this 18th day of June, 1956.

Margie Cooper
 Notary Public

My commission expires: 1-30-57.



RECORDED
 STATE COMMISSION
 JUN 21 1956

PLUGGING
 FILE SEC 18 T. 11 R. 16W
 BOOK PAGE 72 LINE 29

CONSERVATION
 Wichita, Kansas