

15-051-02057-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 19 Twp. 11 Rge. 16 (E) (W) x
Location as "NE/CNW%SW%" or footage from lines C of N/2 NW SE
Lease Owner Okmar Oil Co.
Lease Name Potter Well No. #4
Office Address 1130 Wichita Plaza Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 1-20-67 19
Plugging completed 1-23-67 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3465' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3370', mixed and ran 5 sacks cement thru dump bailer.
Mudded hole to 470', set 20' rock bridge. Filled hole with 6 yards ready-mix from 450' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1967
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 27 day of January, 19 67
October 1968
Sidney D. Miller
Notary Public.



DRILLER'S LOG

15-051-02057-0000

COMPANY: HUBER & FERGUSON
CONTRACTOR: J. M. HUBER
FARM NAME: #4 POTTER "A"

LOCATION: C N/2 NW SE, 19-11S-16W
Ellis County, Kansas

COMMENCED: 5-28-49
COMPLETED: 7-20-49

ELEVATION: 1862
PRODUCTION: Physical Potential.
77 barrels oil per
day plus 9% water.

CASING USED: 8" at 1040' with 500 sacks.
5" at 3463' with 125 sacks.

Sandy Shale	100
Red Bed & Shale	400
Shale-Shells-Red Bed	1040
Lime-Shale-Red Bed	1345
Salt-Shale & Shells	1575
Lime & Shale	2030
Lime	2100
Lime & Shale	2195
Shale-Sandy Shells	2365
Shale & Lime	2950
Lime-Cherty	2985
Lime-Broken	3001
Lime & Shale	3030
Lime	3151
Lime & Shale	3180
Lime	3251
Lime & Shale	3286
Total Depth	3463

SAMPLE TOPS:

	D.S.T. 2983-3001, open 25 minutes, died in 20 minutes, recovered 6' of mud, no bottom hole pressure.
Heebner	3023
	D.S.T. 3045-65, open 25 minutes, recovered 60' of mud.
Toronto	3045
Top Lansing	3072
	D.S.T. 3113-51, open 35 minutes, died in 30 minutes, recovered 30' of mud, no bottom hole pressure.
Cherty Conglomerate	3338
Shaley Conglomerate	3346
Simpson Shale	3370
Simpson Sand	3373
Arbuckle	3382
	D.S.T. 3383-90, open 50 minutes, recovered 10' of water, 10' of mud, 15' of heavy oil cut mud. Bottom hole pressure-700#.
	Perf. 12 holes 3486-90, Acidized with 500 gallons. Bailed 10 times per hour, 4.7 barrels of oil per hour, small show water.

PHYSICAL POTENTIAL - 77 barrels oil per day plus 9% water.

3382-9.
5 hrs 41 min.

COMPLETE

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1967

CONSERVATION DIVISION
Wichita, Kansas