

15-051-03665-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 19 Twp. 11 Rge. 16 (E) (W) X
Location as "NE/CNWxSWx" or footage from lines E/2 NW/4 NE/4
Lease Owner Okmar Oil Company
Lease Name Potter SWD Well No. 9
Office Address 1130 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) SWD
Date well completed June 12, 19 56
Application for plugging filed September 7, 19 67
Application for plugging approved September 8, 19 67
Plugging commenced September 8, 19 67
Plugging completed September 15, 19 67
Reason for abandonment of well or producing formation SWD no longer used

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3714 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	1032	8 5/8	1032	NONE
		0	3592	5 1/2	3592	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 3415'
Mud 3415 - 1000'
200 sks cement 1000 - 250'
2 yards ready mix 250 - surface

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Okmar Oil Company
Address Box 723, Hays, Kansas 67601

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Robert M. Beren, Division Mgr. (employee of owner) or (owner or operator) of the above-described well, being first-duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1130 Wichita Plaza, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 1 day of November, 19 67

[Signature]
Jeannine ReQua
Notary Public.



My commission expires March 12, 1970

RECEIVED
STATE CORPORATION COMMISSION

15-051-03665-0000

SEP 8 1967

CONSERVATION DIVISION
Wichita, Kansas

OKMAR OIL CO.
Potter #9

C/2 NW NE 19-11S-16W
Ellis County, Kansas

Sierra Petroleum Co., Inc. - Contr.

Elev: 1833 DF

Total Depth: 3714'

Drilled 131' into Arbuckle
for use as a Salt Water
Disposal Well

Comms: 5/30/56
Comp: 6/12/56

Casing:

8 5/8 @ 1032
5 1/2 @ 3592

Cement:

With 450 sks Comm Cement
With 300 sks Cement

FORMATION

DEPTH

Shale & streaks of Flint Rock	95
Grey Shale & shells	325
Red Bed & shale	450
Sand & shale	520
Red Bed	548
Sand & shale	670
Red Bed & shale	1021
Anhydrite	1045
Red Bed	1250
Salt & shale	1460
Shale & shells	1510
Lime & shale	2860
Shale & shells	2915
Lime	3023
Shale	3044
Lime	3183
Lime & shale	3240
Lime	3348
Conglomerate	3583
Arbuckle	3714

$$\begin{array}{r} 1835 \\ 1021 \\ \hline 614 \end{array}$$

$$\begin{array}{r} 3583 \\ 1835 \\ \hline 1648 \end{array}$$

3714

Tops:	Anhydrite	1021
	Hebner	3020
	Toronto	3042
	Lansing	3065
	Arbuckle	3583

STATE OF KANSAS }
COUNTY OF RUSSELL } ss:

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Honaker

Subscribed and sworn to before me this 14th day of June, 1956.

Margie Cooper
Notary Public

My commission expires: 1-30-57