

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-02056-0000

API NUMBER 8-22-48

LEASE NAME Potter

WELL NUMBER 3

SPOT LOCATION SW ^{NW} ~~NE~~ SE ^{AMB} ^{KCC}

SEC. 19 TWP. 11 RGE. 16 (E) or (W)

COUNTY Ellis

Date Well Completed 8-22-48

Plugging Commenced 3-3-90

Plugging Completed 3-5-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well Oil
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 3400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	1025	8 5/8		
	Casing	0	3395	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. TIH with 3 7/8 flat bottom mill, 3 drill collars bumper sub, Tag at 635'. Mill to 677'. TOH with tubing, DC, and mill. TIH with tubing and collar. Tag at 643'. Mill to 650'. Pump 100 sks common followed by 65 sks 65/35 pos, 6% gel, 1/4 celflake. Circulate to surface. Hook up to casing and pump 15 sks 65/35 pos, 6% gel, 1/4# celflake. 10' of 8 5/i pumped out of ground. Cement 5' from surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245
Address Box 723 Hays, Kansas 67601

BJ Titan cementer

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford
(Address) Box 723 Hays, Mo. 67601

ROSEMARY SMITH
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXP. MAY 1, 1991

SUBSCRIBED AND SWORN TO before me this 6 day of March, 19 90

Rosemary Smith
Notary Public

MY APPT. expires: 5-1-1991