

LEASE NAME Slimmer

WELL NUMBER 2

SPOT LOCATION SE NE NW

SEC. 19 TWP. 11 RGE. 16 (E) or (W)

COUNTY Ellis

Date Well Completed 11-56

Plugging Commenced 2-14-90

Plugging Completed 2-14-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3337

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	1023	8 5/8		
	Casing	0	3334	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Trip in with tubing to 3100'. Spot 125 sks. 65/35 8% gel. Pull tubing to 1262'. Mixed 375 sks. 65/35 8% gel. Did not circulate to surface. Haul out 250 sks. more 65/35 8% gel. Run tubing to 500' Mix 65 sks cement circulate. Pull tubing. Hook up to 5 1/2 casing and squeeze in 25 sks. 300#. Shut in. Total used 590 sks.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245
Address Box 723 Hays, Kansas 67601

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford
(Address) Box 723 Hays, Ks 67601



SUBSCRIBED AND SWORN TO before me this 15 day of February, 1990
Rosemary Smith
Notary Public

My Commission expires: 5/1/1991 STATE CORPORATION COMMISSION

FEB 16 1990

Form CP-4
Revised 06-83