

15-051-20903-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1973
06-22-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delaney of R & W Oil has this

date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Co., Inc.

Complete Address: 603 Union Center Wichita, Ks.

Lease Name: Craig Well No. 1

Location: SE SE SW Sec. 9 Twp. 11 Rge. (E)(W) 16

County: Ellis Total Depth 3430' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Delaney was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 480' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/3 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. L. Wessely
Conservation Division Agent