

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission  
 CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 26 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Weiler of Shields Drlg. has this

date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: ProspectOil Inc. & Shiekds

Complete Address: 811 Union Center Wichita, Ks.

Lease Name: Craig Well No. 1

Location: NE NW SW Sec. 9 Twp. 11 Rge. 16 (E)(W) X

County: Ellis Total Depth 3465 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Weiler was instructed to plug the well as follows:  
 Gun pits, circulate heavy mud, set cementing plug at 540' and displace  
 70 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and  
 displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
 plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
 with 2 sc cement.

Very truly yours,

Leo J. Massie  
 Conservation Division Agent