

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION  
(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Jerry Helberg of Helberg Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Isern-Schultz Oil & Gas, Inc.

Complete Address: Box 486, Ellinwood, Kansas 67526

Lease Name: Marshall Well No. #12

Location: NE NE NE Sec. 25 Twp. 11 Rge. 18 (E) (W)

County: Ellis Total Depth: 3491'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Helberg was instructed to plug the well as follows:

8 5/8"-270' s.p. cuc. w/140 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 250' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement.

Circulated 10 sacks of cement in rat hole.

Very truly yours,

Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1982  
05-24-82  
CONSERVATION DIVISION  
Wichita, Kansas