

15-051-22625-0000

State of Kansas



FORM GP-2

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Dana Hewett of Emphasis Oil Operations has this date requested permission to plug the following described well:

Operator's Full Name: Jolly J, Inc.

Complete Address: Box 572, Russell, Ks. 67665

Lease Name: Cress Well No. #1

Location: NE/SW/SE Sec. 18 Twp. 11 Rge. 16 (E) (W)

County: Ellis Total Depth: 3400'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Dana Hewett was instructed to plug the well as follows:

8 5/8"-250' s.p. cuc. w/150 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-6% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

- 1st plug @ 660' w/70 sacks cement
- 2nd plug @ 240' w/40 sacks cement
- 3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement
- 10 sacks of cement in rat hole.

Very truly yours,

[Signature]  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

NOV 2 1981

CONSERVATION DIVISION  
Wichita, Kansas