



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
3-5-1973  
MAR 5 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Russ Sullivan of Russ Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Gano Well No. A-2

Location: SW-SE-NW Sec. 13 Twp. 10 Rge. (E)(W) 26

County: Sheridan Total Depth 4110 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sullivan was instructed to plug the well as follows:

253'--8 5/8" Surface casing, cement circulated.  
4110'--4 1/2" Production casing cemented on bottom. No plug back indicated top of perforations @ 3848'.

Push plug to 3800', sand to 3750' and set 4 Sx. cement with dump bailer.  
Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

*H. L. Nichols*  
Conservation Division Agent