

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Paul Stevens of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Stevens guarantees payment of the plugging fee.

Operator's full Name: Monarch Oil & Gas Company,

Complete Address: 1429 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Gano Well No. 1

Location: SW-SE-NE Sec. 13 Twp. 10 Rge. (E)(W) 26

County: Sheridan Total Depth 4060' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Stevens was instructed to plug the well as follows:

213'--8 5/8" Surface casing, cement circulated with 185 Sx.  
Top of Dakota section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1275' and displace 100 Sx.  
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
 STATE CORPORATION COMMISSION  
 6-23-1969  
 JUN 23 1969

Very truly yours,

CONSERVATION DIVISION  
 Wichita, Kansas

M. S. Nichols  
 Conservation Division Agent