

15-051-05030-0000

Form CP-3
Rev. 6-4-68

KANSAS

X
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company
 Complete Address Box 553 Russell, Kansas 67665
 Lease Name Slimmer "A" Well No. 3
 Location SE. SE NW Sec. 19 Twp. 11 Rge. (E) (W) 16
 County Ellis Total Depth 3420'
 Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Knight Casing Pulling
 Address Box 405 Chase, Kansas 67524 License No. 436
 Operation Completed: Hour 11:45 A Day 29 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 3420' 8 5/8 csg set at 1065' cwc 500 sk.
5 1/2 csg set at 3420' cw 150 sk cmt.
5 1/2 csg PBTB 3381' and perf. (3354)
 Set 5 1/2 wood plug at 3250' -poured 10' sd -Dumped 5 sk cmt W/dump bailer. (3200-3259)
 Cutoff and recovered 2305' of 5 1/2 csg.
 Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug
 and pumped 80 sk Halco-Light by HOWCO. SI pres. 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3-3-72
INV. NO. 5268-12