

15-051-03665-0000

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 25 1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Okmar Oil Company

Complete Address: 1130 Wichita Plaza Wichita, Kansas

Lease Name Potter Well No. 9

Location E/2 NW NE Sec. 19 Twp. 11 Rge. 16 (E) (W) X

County Ellis Total Depth 3714

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Co. Tools Sun cementing Co.

Address: Hays, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 4 P Day 22 Month 9 Year 1967

The Above well was plugged as follows:

Total Depth 3714' 8 5/8 csg set at 1027' cwc 450 sc.

5 1/2 csg set at 3592' cw 300 sc cement.

5 1/2 csg perf. at 1027 and circ to surface with 200 sc cement.

200' of cement lined tubing stuck on bottom.

No. pipe recovered.

9-8-67 Pumped 200 sc cement down 5 1/2 csg and shutin.

9-11-67 ran wire line- top of cement 250'.

Filled with mud to 100' set plug and cemented to base of cellar W/ 12 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo J. Massey  
Well Plugging Supervisor

DATE 9/26/67

INV. NO. 6380-u