

15-051-03663-0000

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 7th SESE  
LOCATION NW NE SE  
SEC. 19 TWP. 11 RGE. 16 W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. B-1 Lease Potter 405 Schwider Bldg.  
Operator Okmar Oil Co. Address Wichita, Kans  
Field Bemis County Ellis  
Total Depth 3402 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 240' circulated with cemet - 5 1/2" at 3376' with  
150 sax cement behind.  
Filled with sand to 3360', set 4 sax cement with dump bailer,  
pulled 2646' 5 1/2', filled with mud to 240', set rock and 15  
sax cement, mud to 35', set rock and 10 sax cement to bottom  
ceklar.

**PLUGGING**  
FILE SEG 19 T 11 R 16  
PAGE 35 17

STATE CORPORATION COMMISSION  
OCT 29 1952  
CONSERVATION DIVISION  
Wichita, Kansas

*John P. ...*  
District Conservation Agent  
Date 10-26-52