

15-051-02063-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 17 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 1130 Wichita Plaza Wichita, Kans

Lease Name Potter Well No. 10

Location E $\frac{1}{2}$  SW NE Sec. 19 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3412

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing P.,lling

Address: Great Bend, Kans License No. 399

Operation Completed: Hour 5PM Day 14 Month 3 Year 64

The Above well, was plugged as follows:

8 5/8" 1082' circulated with cement - 5 1/2" 3404' with 150 sax cement.

Sand back to 3390', set 4 sax cement with dump bailer - pulled 2620' 5 1/2"

80 988' circulated hole with heavy gel mud through 5 1/2" at 988' (25 sax Gel)

displaced 40 sax cement through 5 1/2" at 385', heavy mud to 40', set bridge

and filled to bottom cellar with cement.

Mudding and cementing by Southwest Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 3/17/64  
INV. NO. 8494-W