

15-051-02062-0000

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1961

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: CE $\frac{1}{2}$ W $\frac{1}{2}$ NE Sec. 19 Twp. 11 Rge. _____ (E) _____ (W) 16

Name of Field: _____ Total Depth: 3393

I have this date completed supervision of plugging of:

Lease Name: Potter Well No. 8

Operator's Full Name: Okmar Oil Co

Complete Address: 820 Union Natl Bk Bldg Wichita, Kansas

Plugging Contractor Glenn & Smith

Address: Ellinwood, Kansas License No. 396

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 14 Month 11 Year 61

The above well was plugged as follows:

8 5/8" 107' circulated with cement. 5 1/2" 3391' with 150 sax cement.
Set 5 sax cement on bottom with dump bailer - pulled 2550' 5 1/2" to 500',
circulated hole with heavy mud through 5 1/2" at 500' (27 sax Gel), displaced
20 sax cement through 5 1/2" at 500', heavy mud to 170', displaced 20 sax
cement through 5 1/2" at 170', heavy mud to 35', set 10 sax cement to bottom
cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 11/28/61
INV. NO. 4096-u