

15-179-20319-00-00

Form CP-3
Rev. 6-4-68

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8-21-1972
AUG 21 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,
 Complete Address R. R. #2, Victoria, Kansas.
 Lease Name Gano Well No. 3
 Location SE-SE-SW Sec. 13 Twp. 10 Rge. (E) (W) 26
 County Sheridan Total Depth 3870'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated
 Plugging Contractor Above
 Address License No.
 Operation Completed: Hour 10:30 PM Day 10 Month 8 Year 1972

The above well was plugged as follows:

236'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 8/21/72
INV. NO. 6205-W