

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
11-3-1975
NOV 3 1975
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil Inc.
Complete Address RT. 2 - Box 28. Victoria Ks.
Lease Name Gano Well No. B-7
Location SW-NE-NE Sec. 13 Twp. 10 Rge. 26 (E) (W) X
County Sheridan Total Depth 4100'
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Dreiling Oil Inc.
Address RT. 2. Box 28. Victoria Ks. License No. _____
Operation Completed: Hour 9:00 AM Day 31 Month Oct. Year 1975

The above well was plugged as follows:

KB. 2567' Dak Top. 1550' Sp. 200' of 8 3/8 cwc. 165 sx. cem.
4086' of 4 1/2" casing set w/ 225 sx. cem. Top Cem. 3200
Top Perf 3964' Bottom Plug set. w/ 50' of sand & 4, sx. cem.
Recovered 1812' of 4 1/2" casing. Pumped down. 8 5/8"
3.5x Hulls. 80 sx. cem. 50% Pozmix 67. Gel.
13 sx Gel. Release Plug. & 50 sx. cem. 50% Pozmix 67. Gel.
Max. Pres. 200 Lbs., Closing Pres. 200 Lbs.
Sun Cementing

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Jillie Batthoray
Well Plugging Supervisor

DATE 11/3/75
INV. NO. 2171-W