

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
3-5-1973  
MAR 5 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Gano Well No. 5

Location SW-SW-NW Sec. 13 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 4090'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 12:00 M Day 28 Month 2 Year 1973

The above well was plugged as follows:

242'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1040'. This well was drilled as a rotary hole and temporarily abandoned.

Squeezed well with 5 sacks hulls and 9 sacks gel and followed with 110 Cu. Ft. cement from 1275' to 950', then 17 sack gel from 950' to 275' and followed with 30 Cu. Ft. cement from 275' to 200' then 4 sacks gel from 200' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. (Mudding and cementing operations performed by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Dechels  
Well Plugging Supervisor

INVOICED  
DATE 3/5/73  
INV. NO. 4095-W