

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED

STATE CORPORATION COMMISSION

11-3-1975
NOV 3 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Drieling Oil Inc.

Complete Address RT. 2 - Box 28 - Victoria Ks.

Lease Name Gano. Well No. B. #2

Location NE-NE-SE Sec. 13 Twp. 10 Rge. 26 (E) (W) X

County Sheridan Total Depth 4075

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Drieling Oil Inc.

Address RT. 2 - Box 28 - Victoria Ks. License No.

Operation Completed: Hour 11:30 AM Day 31 Month Oct. Year 1975

The above well was plugged as follows:

KB. 2557' Dat Top. 1500' S.P. 197' of 8³/₈ c.w.c. 150 sx cem.
4055' of 4¹/₂" casing. set w/ 225. sx. cem.
Top of Cem. 3128' Top Pert 3814' Bottom Plug set @
3700' w/ 50' of sand + 4. sx. cem. Recovered 1504' of 4¹/₂"
Pumped down 8³/₈ casing. 3 sx Hulls. 80 sx cem
50/50 Perm 67 Gel. 12 sx Gel. Release Plug. +
50 sx. cem. 50 Perm 67 Gel. Closing Pres. 150 Lbs.
Max. Pres. 150 Lbs. 547. Cementing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Gilbert Palthogor
Well Plugging Supervisor

DATE 11/3/75

INV. NO. 2172-W