


KANSAS



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
6-15-1972  
JUN 15 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Gano Well No. 2

Location SE-SW-NW Sec. 13 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 4080'

Abandoned Oil Well        Gas Well   X   Input Well        SWD Well        D & A   X  

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 2:30 AM Day 11 Month 6 Year 1972

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 1075'.

---

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 110 Cu. Ft. cement  
thru DP from 1300' to 975'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement  
To bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Deibel  
Well Plugging Supervisor

INVOICED  
DATE 6/15/72  
INV. NO. 5880-W