

15-179-20311-00-01

Form CP-3  
Rev. 6-4-68

KANSAS

*af* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
3-5-1973  
MAR 5 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Gano Well No. A-2

Location SW-SE-NW Sec. 13 Twp. 10 Rge. (E) (W) 26

County Sheridan Total Depth 4110'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Russ Casing Pulling, Incorporated,

Address Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 11:00 AM Day 28 Month 2 Year 1973

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated.

4110'--4 1/2" Production casing cemented on bottom. No plug back indicated. Top of perforations @ 3848'.

Pushed plug to 3800', sanded back to 3750' and set 4 Sx. cement with dump bailer.

Pulled 4 1/2" casing (2520) and squeezed well initially with 5 sacks hulls and 9 sacks

gel and followed with 110 Cu. Ft. cement from 1275' to 950' then 17 sacks gel from

950' to 275' and followed with 30 Cu. Ft. cement from 275' to 200' then 4 sacks gel

from 200' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar.

(Mudding and cementing operations by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *K. L. Dickels*  
Well Plugging Supervisor

INVOICED

DATE 3/5/73

INV. NO. 7094-W