

6 070861

9-17

051-24,689 -0000

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE, SEC. 9, T 11 S, R16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

330 feet from S section line

2310 feet from E section line

Operator: Eric Waddell Co.

Lease Name Craig Well # c-1

Name & Address: Box 349

County Ellis 110.50

Well Total Depth 3400 feet

Natoma, Ks. 67651

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well Gas Well Input Well SWD Well D&A x x

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling License Number 5422

Address 801 Union Center Wichita, Ks. 67202

Company to plug at: Hour: PM Day: 17 Month: Sept Year: 19 90

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling (phone)

were: 8 5/8 s.p. 207 ft. cwc w/130 sks 60/40 poz 2% gel 3% ca cl, by Allied.

Conglomert well, elv. 1920. Anhy 981. No circulation problems. Mud condition 44 vis.

10. weight, 11 water loss. Proposal 215 sks 60/40 poz 6% gel 3% cc. 1 sk f.c. and 8 5/8

plug. Spot with drill stem, circ, heavy mud between all plugs at 990 - 100 sks at 540-

w/1 sk f.c. - 40 sks at 250 - 10 sks w.p. at 40 ft. 15 sks in rathole (cir)

Plugging Proposal Received by *M.J. Schmidt* MJS (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 4:00PM Day: 17 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Abercrombie Drilling ordered 215 sks

60/40 poz 6% gel 1sk f.c. and wiper plug. Spotted with drill stem, circulated hole, heavy mud between all plugs. No arb. 1st plug at 990 w/25 sks cement.

2nd plug at 540 w/100 sks cement w/1 sk f.c. 3rd plug at 250 w/40 sks cement.

4th plug w.p. at 40 w/10 sks cement. 15 sks in rathole circulate by Allied.

RECEIVED STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this form.)

09-26-90 SEP 26 1990

INVOICED

DATE 10-2-90

INV. NO. 29496

J.S.

Signed *Marion J. Schmidt* (TECHNICIAN)

Marion J. Schmidt