

4 060162

2-12

205
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-24,663-0000

NW NW NE, SEC. 16, T 11 S, R 16 W/E

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6725

Lease Name Craig "C" Well # 1

Operator: Eric Waddell Co.

County Ellis 110.50

Name & Address Box 349

Well Total Depth 3400 feet

Natoma, KS 67651

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXXX

Other well as hereinafter indicated _____

Plugging Contractor _____ Co Tools _____ License Number _____

Address _____

Company to plug at: Hour: _____ Day: 1:00PM Month: February Year: 19 91

Plugging proposal received from Eric Waddell

(company name) Eric Waddell Co. (phone) _____

were: Order 375 sxs, 65/35pos 8%gel and hulls.

Shot off casing at 1030' but stuck in hole after pulling landing joint-of 10'

Delayed completion and proved non-commercial.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXX Part _____ None _____

Operations Completed: Hour: 6:15PM Day: 12 Month: February Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" to 218', 4 1/2" to 3459'. Shot off and pulled 4 1/2" to 1020' for total recovery of 10' of casing. Pumped 100sxs. cement down casing at 1020' Perf. at 970' and pmp 150 sxs. cement with partial displacement up annulus. Tied onto annulus and pumped 125 sxs. cement. Casing Max 800# SIP 200# Annulus Max 400# SIP 100#

Remarks: Allied Cementing
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 3-6-91

Signed [Signature]
(TECHNICIAN)

INV. NO. 31019 2-12 MAY 03 1991

Herb Deines