

6010595

2-19-88 15-051-01076-0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Old Well

SE NE <sup>SW</sup> ~~NW~~, SEC. 16, T 11 S, R 16 ~~W~~  
~~4290~~ 1650 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Craig Well # 3-SWD

Operator: Chief Drilling Co. Inc.

County Ellis 108.84

Name & Address 905 Century Plaza

Well Total Depth 3349 feet

Wichita, Kansas

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 956

Abandoned Oil Well Gas Well Input Well X SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Same License Number 5886

Address Same

Company to plug at: Hour: 10:00 AM Day: 19 Month: Feb Year: 19 88

Plugging proposal received from Gary Lindenmuth

(company name) Same (phone)

were: Order 50 sks Common Cement w/2% Gel and 300 sks cement 65/35 Pozmix 10% Gel

2% Econolite and 300# Hulls. 4 1/2" casing at 3348'. Perf 3015' - 3196'. 2 1/2" tubing and packer at 3000', pulled 1320' - 1680' of tubing and packer stuck in the well.

Plugging Proposal Received by Dale F. Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:00PM Day: 19 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing to 1200'. Pumped down tubing 50 sks cmt w/2% Gel. Pulled 500' tubing. Pumped down tubing, C.W.C. Pulled tubing. Tied onto casing. Press to 900#. Total Econolite 35 sks and 50# of Hulls. Tied onto 8 5/8" pumped down 265 sks Econolite w/150# Hulls. Closed w/500# pressure. Max 600#

RECEIVED  
STATE CORPORATION COMMISSION  
RCWD  
MAR - 2 1988  
03-02-88  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: B. J. Titan Cement Co.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did /- observe this plugging.

DATE 3-2-88

Signed Dale F. Balthazor (TECHNICIAN)

Dale F. Balthazor

INV. NO. 19954

2-19.