

6 030847

JAN 16 1987 15-051-20305-0000

API NUMBER 19-

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SUNRISE, SEC. 17, T 11 S, R 16 W  
1650 feet from S section line  
2310 990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name CHESNEY Well # B-1

Operator: VINCENT OIL CORP.

County FELLIS 108.10

Name & Address: 125 N. MARKET SUITE 1110  
WICHITA, KANSAS  
67202

Well Total Depth 3326' feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 965'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ALLIED CMT CO License Number \_\_\_\_\_

Address RUSSELL, KANSAS.

Company to plug at: Hour: PM Day: 16 Month: 1 Year: 19 87

Plugging proposal received from CLINT BASE.

(company name) VINCENT OIL CORP. (phone) \_\_\_\_\_

was: 8 5/8 SET @ 965' w/ 500 SX. CWC. 5 1/2 SET @ 3325' w/ 125 SX.

BACKSIDE 8 5/8 - 5 1/2 ANNULUS WAS FULL OF DRY HARD MATERIAL

OPEN HOLE 3325 - 26' ORDER 200 SX. ATN 6 5/8 SPAR 10 1/2 GEL 3 1/2 CU

BX. HULLS ALLIED CMT. CO. B & W WATER TRUCKS

Plugging Proposal Received by Carl Goodnow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12: PM Day: 16 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT MIX & Pump DOWN 5 1/2" CSG. 80 bbl <sup>SLURRY</sup> CMT MIX. 160 SX  
CMT MIX. w/ 4 SX. HULLS MIXED IN. MAX. PSI 2600# CLOSE IN 1500# PSI  
MIX & Pump DOWN 8 5/8 - 5 1/2 ANNULUS 1 Bbl CMT. SLURRY 2 SX. ATN  
BLEW OFF CSG. SEREW CAP & RUBBER. REPAIRED HEAD  
COULDN'T PUMP INTO ANNULUS. Plug. COMPLETE  
ALT. L. COMPLETION.

Remarks: (If additional description is necessary, use BACK of this form. 01-22-87 JAN 22 1987)

INVOICED (did not observe this plugging.)

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

DATE 1-22-87

Signed Carl Goodnow (TECHNICIAN)

INV. NO. 15992