

See letter attached.

271

6080022

Plugged with Conservation Fee Funds, R

API NUMBER 15-051-01,008-0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SW 1/4 SEC. 17, T 11 S, R 16 W

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

Operator License # 9451

Lease Name Chesney Well # 1 own

Operator: Baker Oil Operations

County Ellis 110.50

Name & Address Drawer B

Well Total Depth 3400 feet

See above Plainville, Ks 67663  
913 434 2028

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 979

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Zeigler Well Service License Number \_\_\_\_\_

Address Box 873 Russell Ks 67665 913 483 2041

Company to plug at: Hour: 8: A Day: 29 Month: July Year: 19 86

Plugging proposal received from None

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: Find current total depth - top of bottom 50sx pumped plug 2650'

Run tubing below surface pipe -

Circulate cement to surface - econolite -

Pressure up on 8 5/8 casing with cement

Check for cement loss -> by KCC

Plugging Proposal Received by Don Butcher (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:55A Day: 29 Month: July Year: 19 86

ACTUAL PLUGGING REPORT Total depth by wireline 1100 ft. Ran 990 feet of

2 1/2 tubing. Cemented with full returns. Cut circ at 90 bbls with

3 sx hulls scattered in last 15 bbls. Casing Capacity 63 bbls.

90 bbls equivalent to 150 sx. Pulled tubing and pressured to

500 psig while pumping in an additional 50 sx. Final shut-in

pressure 375 psig - Job Complete - Ordered, Used 200sx econolite

Remarks: \_\_\_\_\_ (If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG - 6 1986

Signed Don Butcher (TECHNICIAN)

14637

7/31/86

REV. NO. 7-29