

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02047-00-00  
Spot: CSESWNW Sec/Twnshp/Rge: 17-11S-16W  
2970 feet from S Section Line, 4290 feet from E Section Line  
Lease/Unit Name: CHESNEY Well Number: 1  
County: ELLIS Total Vertical Depth: 3380 feet

Operator License No.: 6772 Conductor Pipe: Size \_\_\_\_\_ feet:  
Op Name: WEIGEL, V. FRANCIS - FAMILY PARTNE Surface Casing: Size 8.625 feet: 1022  
Address: PO BOX 219 Production: Size 5.5 feet: 3377  
GORHAM, KS 67640 Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

8109.85

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2001 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: According to KCC Rules & Regulations.  
Ordered 250 sxs cement and 400# hulls.  
Plug thru casing.

Plugging Proposal Received By: ROGER MOSES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/22/2001 3:30 PM KCC Agent: ROGER MOSES

**Actual Plugging Report:**  
8 5/8" S.P. at 1022'. 5 1/2" casing at 3377'.  
Sanded off bottom with 5 sxs cement.  
Shot casing off at 2448'.  
Pulled casing to 1600' - pumped 100 sxs cement with 300# hulls.  
Pulled casing to 1100' - pumped 40 sxs cement with 100# hulls.  
Pulled casing to 600' - pumped 30 sxs cement.  
Pulled casing to 200' and circulated 30 sxs to surface.  
Total of 200 sxs 60/40 pozmix with 10% gel and 400# hulls.

RECEIVED  
SEP 04 2001  
09-04-01  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: CSG

District: 04

Signed Roger L. Moses  
(TECHNICIAN)

**INVOICED**  
DATE 9-4-01  
INV NO. 2002060323

Form CP-2/3

AUG 28 2001

FRONTIER OIL

#1 CHESNEY

17-11-16W  
SE SW NW

Contr. TRANS ERA PETROLEUM

ELLIS

County

E 1820 RB Comm. 4-15-56

Comp. 6-15-56

IP 81 BOPD/ARB

PP

Tops	Depth	Datum
ANH	1012	808
HEEB	2971	-1151
LANS	3015	-1195
B/KC	3256	-1436
CONG	3299	-1479
SIMP	3327	-1507
ARB	3375	-1555
TD	3380	-1560

Casing

8" 1022 DST 3035-55/1 HR, 30' H OC  
MUD, BHP 0#

5" 3377 DST 3055-75/3 HRS, 120' GAS,  
60' MUD, BHP 500#

DST 3075-95/1 HR, 8' MUD, NS, BHP 0#

DST 3221-37 1/2 HR, 8' MUD, BHP 875#

DST 3299-3310/1/2 HR, 6' MUD, BHP 0#

DST 3352-72/1 HR, 120' GAS, 210' OIL,  
BHP 750#

DST 3376-80/1 HR, 400' OIL  
CO TD, SWB 5 BOPH, NAT

LEIB POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

17-11-16W  
SE SW NW