

6 041304

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA

6-17 051-20012-0000 187 R
SW SW SW, SEC. 17, T 11 S, R 16 W/E
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Chesney 'A' Well # 1

Operator: Vincent Oil Corporation

County Ellis 107.54

Name & Address 100 N. Main

Well Total Depth 3309 feet

Suite 500

Conductor Pipe: Size - feet -

Wichita, Kansas 67202-1308

Surface Casing: Size 8 5/8 feet 965' w/500 sxs.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B.J. Services, Inc. License Number

Address Hays, Kansas 67601

Company to plug at: Hour: 10:00 A.M. Day: 17 Month: 6 Year: 19 91

Plugging proposal received from Pat Livingston

(company name) Vincent Oil Company (phone)

were: 5 1/2" casing set at 3309' w/100 sks. cement: perms. at 3309' O.H. to 3313';

Perf. anhy. at 975'. C.I.B.P. @ 3200'. Ordered 425 sks. 60/40 poz.

8% gel. w/1/4 lb. flocele.

Plugging Proposal Received by Dennis L. Hanel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:45 P.M. Day: 17 Month: 6 Year: 1991

ACTUAL PLUGGING REPORT R.I.H. w/tubing to 3150'; Spot 125 sxs. cement to circulate

at surface: Pulled tubing to 1000'; spot 125 sxs. cement to circulate cement.

P.O.O.H. w/tubing: Hooked up to 5 1/2" casing, squeezed 175 sxs. cement to circulate

cement out of 8 5/8 S.P.: Shut-in same, squeezed casing to 500# Max. P.S.I.

S.I. 400#

RECEIVED STATE CORPORATION COMMISSION

RCVO
JUL 01 1991
07-01-91

Remarks: (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

did observe this plugging.

INVOICED

Signed Dennis L. Hanel (TECHNICIAN)

DATE JUL 22 1991

INV. NO. 32341

SEP 27 1991

FORM CP-2/3 Rev.01-84