

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00102-00-01
Spot: NENWSW Sec/Twnshp/Rge: 17-11S-16W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: LIEB Well Number: 1
County: ELLIS Total Vertical Depth: 3363 feet

Operator License No.: 6772 Conductor Pipe: Size _____ feet:
Op Name: WEIGEL, V. FRANCIS - FAMILY PARTNE Surface Casing: Size 8.625 feet: 784 250 SX CMT
Address: PO BOX 219 Production: Size 5.5 feet: 3359 150 SX CMT
GORHAM, KS 67640 Liner: Size _____ feet: _____ 8/109.30

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2001 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: According to KCC Rules & Regulations.
Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug thru casing.

Plugging Proposal Received By: ROGER MOSES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 08/19/2001 2:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 784' w/400 sxs cement. 5 1/2" casing at 3359'.
Tied to 5 1/2" casing - pumped 275 sxs cement with 500# hulls to Max. P.S.I. 600#. S.I.P. 200#.
Tied to 8 5/8" S.P. - took no cement. Pressure to 500#.
Total of 275 sxs 60/40 pozmix with 10% gel and 500# hulls.

RECEIVED
RCVD
SEP 11 2001
09-11-01
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. QUALITY TANK SERVICE - WATER.

Plugged through: CSG

District: 04

Signed _____

Roger Moses
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-11-01

INV. NO. 2002060453

SEP 06 2001

FRONTIER OIL

#1 LIEB

17-11-16W
NE NW SW

Contr

ELLIS

County

E 1792 RA

Comm.

Comp.

3-30-56

TP 83 BOPD, NW

Tops	Depth	Datum
ANH	985	807
HEEB	2954	-1162
LANS	2998	-1206
CONG	3288	-1196
SIMP	3324	-1532
ARB	3353	-1561
TD	3363	-1571

Casing
 5" 3359 O W W O
 WAS D & A, 5-9-52:
 DST 3013-43, 45", 10' OCM
 DST 3012-75 1/2 HR, 360' GAS,
 90' H OCM, TR FR OIL
 DST 3356-63 1/2 HR: 90' SL OCM
 BHP 990#:
 NEW:
 5" 3359: CO 3363: SWB 1 BOPH
 NATL: ACID 250: SWB 11 BOPH/8
 FR, NW

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

INDEXER

1792 RA

1792 RA

1792 RA