

4-060654

2-23

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-051-22,778-0000

SW SE NW /4 SEC. 18, 11 S, 16 W  
2970 feet from S section line  
3630 feet from E section line

Operator license# 30762 Lease Thurston well # 1

Operator: Oil Company of America, Inc. County Ellis

Address: 1200 Main - #406 Well total depth 3360 feet  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 984 feet

109,20

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 10:30A.M Day: 23 Month: February Year: 95

Plugging proposal received from: Mike Kelso/Wheez

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 225 sxs. 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

Plugging Proposal Received by: Bruce Basye

Plugging operations attended by agent? All [ ], Part [ X ], None [ ]

Completed: Hour: 2:00P.M, Day: 23, Month: February, Year: 95

Actual plugging report: 8 5/8" to 984'. 5 1/2" to 3360'. Sanded casing to 3270' and spotted 5 sxs. cement with dump bailer. Shot casing loose at 2300' and pulled to 1650'. Mixed and pumped 114 sxs. cement with 200# hulls. Pulled casing to 1025' and pumped 40 sxs. cement with 100# hulls. Pulled casing to 500' and circulated cement with 35 sxs. cement. Pulled casing and topped with 11 sxs. cement. Used 200 sxs. of cement total.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING X. Elevation:

I did not observe the plugging.

INVOICED

DATE 3-8-95

INV. NO. 42388

(agent)

Form CP-2/3

RECEIVED STATE CORPORATION COMMISSION CONSERVATION DIVISION MAR 06 1995