

7-8

4-050290

15-051-03288-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- -

W2 NW SW /4 SEC. 18, 11 S, 16 W
1980 feet from S section line
4950 feet from E section line

Operator license# 5214

Lease: Romine Well # 6

Operator: Lario Oil & Gas Company

County: Ellis 109.33

Address: 301 S. Market
Wichita, Kansas 67202
316-265-5611

Well total depth 3364 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1056 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: _____

Company to plug at: Hour: A.M. Day: 7 Month: July Year: 1997

Plugging proposal received from: Tim Gillogly

Company: _____ Phone: _____

Were: Order 225 sxs 60/40 pozmix - 10% gel - 400# hulls - 14 sxs gel.
8 5/8" set at 1056' w/350 sxs. 5 1/2" set at 3347' w/100 sxs.
Open hole from 3347' - 3364'. Casing leak squeezed at 1230' w/300 sxs.
Dakota 230' - 505'. Anhydrite 1000' - 1030'. Salt 1352' - 1562'.

RCWD 07-18-97
KANSAS CORP COM
RECEIVED
1997 JUL 18 P 1:21

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour 12:00 P.M. Day: 8 Month: July Year: 1997

Actual plugging report: Ran tubing to 3240' - pumped 50 sxs cement and 100# hulls. Pulled tubing to 2590' - pumped 14 sxs gel - pulled tubing to 1560' - pumped 145 sxs cement and 300# hulls. Cement circulated to surface. Pulled rest of tubing - tied onto backside - squeezed with 5 sxs cement at Max. P.S.I. 500#. S.I.P. 200#. Squeezed 5 1/2" casing with 25 sxs cement at Max. P.S.I. 300#. S.I.P. 100#. 07-14-97 cement top at 283' - ran 1 1/2 yards ready-mix to top off.

Remarks: _____

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING Elevation: 1833 GL

I did / did not observe the plugging.

Martin Miller
(agent)

INVOICED

DATE JUL 21 1997

INV. NO. 48606

7-8