

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-23,023-0000

SE SE SW Sec. 18, T 11 S, R 16 (W)

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6272

Lease Name Cress Well # 1

Operator: Corie Oil Company
Name & Box 534
Address Russell, Ks. 67665

County Ellis

Well Total Depth 3470 feet 112.78

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 245

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address _____

Company to plug at: Hour: 9 AM Day: 24 Month: August Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Joe Maes

(company name) Kelso Casing Pulling (phone) _____

were: Order 165 sks cmt 50/50 pozmix 6% 3% cal cl, 20 gel, 5 hulls & 8 5/8" plug

Signed _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 AM Day: 24 Month: August Year: 1984

ACTUAL PLUGGING REPORT 8 5/8" set at 245' w/160 sks 5 1/2" set at 3469' w/50 sks

Top Perf. at 3407' Plugged bottom w/5 sks: cement, sand and 5 sks cmt to 3350'

Shot pipe 1 time and recovered 2000'. Pumped in 8 5/8". 3 sks hulls 25 sks cmt, 15 gel, 70 sks cmt, 5 gel, 1 sk hulls, plug, 70 cmt.

1000 lbs maximum - shut in 300 lbs.

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Signed Gilbert P. Leiker (TECHNICIAN)

DATE 9-7-84

SEP 04 1984

Orders by Gilbert Scheck

FORM CP-2/3 Rev. 9-82

INV. NO. 3571

CONSERVATION DIVISION Wichita, Kansas

SH Aug 31 25