

6 070826

2-14 02065-0000

API NUMBER 15-051-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE NW, SEC. 19, T 11 S, R 16 W

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Slimmer Well # 2

Operator: Okmar Oil

County Ellis 108.45

Name & Address 970 Fourth Financial Center

Well Total Depth 3337 feet

Wichita, Kansas 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1023

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan Co. Tools License Number

Address 1707 E 10 Hays, Ks.

Company to plug at: Hour: AM Day: 14 Month: Feb Year: 19 90

Plugging proposal received from George Jorgenson

(company name) Okmar Oil Co. (phone)

were: 8 5/8" - 1023' s.p. cwc w/450 sks. 5 1/2" casing set at 3334'

w/150 sks cement. Perf 3124' to 3128'. Top of cement 5 1/2" casing at 2730'.

Casing poor. Proposal 400 sks 65/35 poz 8% gel and 5 sks hulls. Pump in with pump truck. Spot through tubing. Run tubing to a minimum of 3000'. Circulate

cement from bottom to top. Shut in under pressure. Load 5 1/2" and 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00PM Day: 14 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT Okmar ordered 500 sks 65/35 poz 8% gel and 5 sks hulls.

(1) Annulus open 2 3/8" tubing at 3100'. Spotted 125 sks cement and 1 1/2 sk hulls and

displaced. 2. 2 3/8" tubing at 1262'. Spotted 375 sks cement w/1 1/2 sks hulls. Ordered another 200 sks cement. (3) 2 3/8" tubing at 500' w/65 sks cement. Cement circulated out of both 5 1/2" casing and 5 1/2" x 8 5/8" annulus. (4) Squeezed 5 1/2" casing w/25 sks cement. Max pressure 300 psig. Shut in at 200 psig.

Cemented by B. J. Titan.

Remarks:

RECEIVED additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION observe this plugging.

INVOICED FEB 25 1990

Signed Marion J. Schmidt (TECHNICIAN)

DATE 2-26-90

Marion J. Schmidt

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3 Rev.01-84