

4-041762

15-051-02067-0000

4-4

API Number: 15-051-97,652

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

W2 SW NW /4 SEC. 19, 11 S, 16 W
3300 feet from S section line
4950 feet from E section line

Operator license# 5447

Lease: Slimmer Well # A-1

Operator: OXY USA, Inc.

County: Ellis

Address: 110 S. Main - #800
Wichita, Kansas 67202

Well total depth 3402 110.56 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1064 feet
w/300 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 4 Month: April Year 1996

Plugging proposal received from: J.D. Hininger

Company: OXY USA, Inc. Phone:

Were: 5 1/2" casing set at 3394' w/100 sxs cement. Perf. at 3187' - 3395'
Ordered 400 sxs. 60/40 pozmix -10% gel plus 500# hulls.
PSTD 3402' - Elev. 1911'

RECEIVED OCM
KANSAS CORP
12 APR 1996

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:00 A.M., Day: 4, Month: April, Year: 1996

Actual plugging report: Squeezed 8 5/8" S.P. with 125 sxs 60/40 pozmix - 10% gel with 200# hulls mixed in cement. Max. P.S.I. 300#. S.I.P. 200#. Squeezed 5 1/2" casing with 275 sxs 60/40 pozmix 10% gel with 300# hulls mixed in cement. Max. P.S.I. 600#. S.I.P. 400#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X Elevation: 1911 GL

I did[] / did not[X] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

APR 18 1996

DATE

INV. NO. 45360

4-4 JUN 27 1996