

4-041518

10-5
15-051-15097-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 9-63

NE NE NE /4 SEC. 19, 11 S, 16 W
4950 feet from S section line
330 feet from E section line

Operator license# 5363

Lease Potter "A" well # 1

Operator: Berexco, Inc.

County Ellis

Address: Box 723
Hays, Kansas 67601

Well total depth 3348 feet ^{108.81}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 172 feet
w/150 sxs.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 5 Month: October Year: 93

Plugging proposal received from: George Jorgensen

Company: Berexco, Inc. Phone: _____

Were: 5 1/2" casing set @ 3346' w/150 sxs. cement. Perf. @ 2990'-3337'
Salt @ 1750' - Anhy. @ 1020' - Dakota @ 510' - T.O.F. @ 1600'.
Pulled and laid out tubing and rods October 4, 1993. Perf. casing
October 5, 1993.
Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All , Part , None

Completed: Hour: 12:00P.M. Day: 5, Month: October, Year: 93

Actual plugging report: Hooked-up to 8 5/8" S.P. Pumped in 15 sxs.
cement. Max. 400#. Hooked-up to 5 1/2" casing.
Pumped in 50 sxs. cement with 200# hulls in cement followed with 8 sxs.
gel, followed with 85 sxs. cement with 200# hulls. Max. 700#.
S.I. 700#.

Remarks: Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL _____

RECEIVED
STATE CORPORATION COM
OCT 18 1993

I did did not observe the plugging.

Dennis L. Hamel
W.D. (agent) CONSERVATION DIVISION
Wichita, Kansas

DATE 10-20-93
INV. NO. 38984