

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03305-00-00  
Spot: CSENESW Sec/Twnshp/Rge: 19-11S-16W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: SLIMMER Well Number: 7  
County: ELLIS Total Vertical Depth: 3505 feet

Operator License No.: 3258  
Op Name: LANSING ENERGY OPERATIONS  
Address: 107 N. MARKET, #1115  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 10.75 feet: 1100 520 SX CMT  
Production: Size 7 feet: 3505 250 SX CMT  
Liner: Size feet:

\$113.91

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/03/2001 2:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOHN BECKER Company: LANSING ENERGY OPERATIONS Phone: (316) 262-7595

Proposed Plugging Method: Ordered 700 sxs Swift Multi-Density cement and 800# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/03/2001 4:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Shot casing off at 3000'.  
Pulled one joint and pumped down 3" tubing with 145 sxs cement with 500# hulls.  
Pulled tubing to 1500' - pumped 115 sxs cement with 300# to circulate cement at surface.  
Perf 7" casing at 1050'. Hooked-up to 7" casing and squeezed 40 sxs cement.  
Casing pressured up to 700#. Did not circulate.  
Perf 7" at 180'.  
Pumped 50 sxs cement to circulate cement out of casing hanger at surface.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 11 2001

CONSERVATION DIVISION

INVOICED  
DATE 7-11-01  
INV. NO. 2002060040

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel  
(TECHNICIAN)

JUL 09 2001

SINCLAIR PRAIRIE OIL CO. #7

34 19-11-16<sup>th</sup>  
SLIMMER A/B SE NE SW


Contr. \_\_\_\_\_ ELLIS \_\_\_\_\_ County

E 1909 Comm. 2-26-49 Comp. 5-20-49 IP 78 BCPD & 70% WTR  
P-I-Y FOT

Tops	Depth	Datum
HEEB	3061	- 1152
LANS	3110	- 1201
SIMP	3381	- 1472
ARB	3401	- 1495
T.D.	3505	- 1596

Casing

10" 1100 PERF 47S, 3399-3410  
 7" 3505 ACID 500  
 SWB .125 BO & 50  
 DW/8 HRS  
 PERF 36S, 3401-10  
 ACID 500  
 SWB 7 BOPH



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

010101

COV 25/26/10/11