

6 030180

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

SENE NE, SEC. 13, T. 10 S, R. 26 W E

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145

Lease Name GANO Well # B-4

Operator: DREILING OIL INC.

County SHERIDAN

Name & Address BOX 1000

Well Total Depth 4090 <sup>132.93</sup> feet

VICTORIA KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67671

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ALLIED CEM. License Number \_\_\_\_\_

Address PLAINVILLE, KANSAS

Company to plug at: Hour: PM Day: 19 Month: 4 Year: 19 84

Plugging proposal received from IVAN EDSALL

(company name) DREILING OIL INC. (phone) \_\_\_\_\_

were: PUMP DOWN 4 1/2 AND 8 5/8 WITH 150SX CEM MIX 20SX GEL  
3SX HULLS LOAD HOLE AND SQUEEZE.  
4 1/2 AND 8 5/8 CUTOFF WITH 8 5/8 COLLAR WELDED ON TO PUMP THROUGH  
PUMPS

50/50002 6 1/2 GEL 3 1/2 CC Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 PM Day: 19 Month: 4 Year: 19 84

ACTUAL PLUGGING REPORT PUMPED DOWN 4 1/2 - 3SX HULLS - 5SX GEL - 60SX.  
CEM. MIX. - 15 SX. GEL - 60 SX. CEM MIX.

PUMPED INTO 8 5/8 30SX. CEM. MIX. PUT ON SWEDGE AND  
PUMPED 30SX. CEM. MIX. TO MAX. PRESSURE 200# SHUT IN 150#  
WENT BACK AND TOPPED OFF WITH 40 SX. CEM. MIX.

Remarks: COMPANY PLUGGING PROCEDURE  
(If additional description is necessary, use BACK of this form)

**INVOICED**  
I (did / did not) observe this plugging.

DATE 4-30-84

Signed Carl Goodrow  
(TECHNICIAN)

DNV. NO. 1296

RECEIVED  
STATE CORPORATION COMMISSION  
4-30-1984  
APR 30 1984  
CONSERVATION DIVISION  
Wichita, Kansas