

3-8 15-179-20395-00-00

6 031510

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1974

NW NE SE, SEC. 13, T 10 S, R 26 W/E

2310 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145

Lease Name Gano B Well # 8

Operator: Dreiling Oil Inc

County Sheridan 132.92

Name & Address Box 1000

Well Total Depth 4090 feet

Victoria, Ks. 67671

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: PM Day: 8 Month: Mar Year: 19 91

Plugging proposal received from Ivan Edsall

(company name) Dreiling (phone)

were: 8 5/8 set at 211 w/160 sks cwc. 4 1/2 set at 4083 w/200 sks. PBDT 4000.

Perf 3850 - 3962. Order 350 sks 65/35 poz 10% gel 500 lbs. hulls.

Allied Cement Co. Company water trucks. Shots at 2200 Anny 1350 Kiowa.

Ran wireline to perfs Hole open.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:30PM Day: 8 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sq 4 1/2 casing w/250 sks cement blend w/500 lbs.

hulls mixed into max psi 800 lbs. Close in psi 300 lbs.

Sq 8 5/8 w/100 sks cement blend to max psi 200 lbs. Close in psi 150 lbs.

Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-11-91

INV. NO. 31473

J.S.

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow

RECEIVED STATE CORPORATION COMMISSION 4-4-1991 APR 14 1991 CONSERVATION DIVISION Wichita, Kansas