

15-051-00936-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mobil Oil Corporation
Complete Address Box 1934, Great Bend, Kansas 67530
Lease Name Potter 'A' Well No. 1
Location SW NW SE Sec. 20 Twp. 11 Rge. (E) (W) 16
County Ellis Total Depth 3316'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Glenn Pipe Pulling
Address Box 156, Ellinwood, Kansas 67526 License No. 686
Operation Completed: Hour 10:30 A Day 29 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 3316' 8 5/8 csg set at 956' cwc 500 sk.
5 1/2 csg set at 3309' cw 100 sk.
Filled 5 1/2 csg W/sd (3316-3290) dumped 4 sk cmt W/dump bailer. (3290-3260)
Cutoff and recovered 2600' of 5 1/2 csg
Filled 8 5/8 csg W/mud to 356' -set rock & sand bridge (365-350)
Filled with readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 7/31/74
INV. NO. 9634-W