

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mobil Oil Corporation
Complete Address Box 1934, Oklahoma City, Oklahoma 73101
Lease Name Potter "A" Well No. 4
Location NE SW SE Sec. 20 Twp. 11 Rge. (E) (W) 16
County Ellis Total Depth 3363'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Glenn Casing Pulling
Address Box 156, Ellinwood, Kansas 67526 License No. 686

Operation Completed: Hour 12 M Day 26 Month 7 Year 1974

The above well was plugged as follows:

- Total Depth 3363' 8 5/8 csg set at 939' cwc 450 sk.
- 5 1/2 csg set at 3361' cw 100 sk cem.
- Filled 5 1/2 csg W/sd (3363'-3340') dumped 4 sk cem W/dump bailer. (3340-3320)
- Cutoff and recovered 2604' of 5 1/2 csg.
- Filled 8 5/8 csg W/mud to 365' -set rock & sand bridge (365'-350')
- Filled with readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 7/29/74
INV. NO. 9613-W